

CASE STUDY

Glasgow, BT Centre

Glasgow

Site upgrade works at BT's Glasgow centre for ICON: new palisade-fenced compounds and entrance gates, car park crash barriers and white lining, and repairs to the site's paths, walkways and boundary walls.

CLIENT	COMPLETED	WORK UNDERTAKEN	CONTRACT VALUE
ICON, for BT Group	2026	Demolition, Fencing & Gates, Masonry Repairs, Crash Barriers, White Lining	£100,000

£100k	150m	144m
Contract value	Palisade fencing installed	Crash barrier installed

Scope of works

The Curley Group was appointed by ICON, working on behalf of BT Group, to bring the external areas of BT's Glasgow centre up to date. Our package ran from August to October 2026 and covered:

- Demolition and removal of the existing fence line
- Installation of 150 linear metres of palisade fencing to form new secure compounds
- New site entrance gates
- Installation of 144 linear metres of crash barrier in the car park
- New white lining throughout the car park
- Remediation works to existing paths, walkways and boundary walls

Fencing, compounds & gates

We took down the old fence line and replaced it with 150 linear metres of galvanised palisade fencing, laid out to form new compounds within the site. New entrance gates were installed to complete the secure perimeter.

Car park safety

In the car park we installed 144 linear metres of crash barrier to protect buildings, pedestrians and equipment, and carried out new white lining to give clear, safe parking and traffic routes.

Paths, walkways & boundary walls

Sections of the site's brick boundary walls had deteriorated, with loose and missing bricks and copings and heavy vegetation growth. We carried out remediation works to the walls, rebuilding damaged sections and finishing them with new copings, alongside repairs to the existing paths and walkways so the whole site is safe and up to date.

Working on a live BT site

The works were delivered to a tight programme on a fully operational BT site. We planned each stage around BT's staff and day-to-day operations, keeping access open and work areas safe so the site could keep running as normal throughout.

On site











Before & after





Corner boundary wall by the site entrance





Street-side boundary wall with new copings

CURLEY GROUP

Talk to us about your next project

Unit 4 Landgate Industrial Estate, Ashton-in-Makerfield, Wigan WN4 0BW

01942 926169

curleygroupltd@gmail.com